



NOTE:

SEE SHEET 2 OF 2 FOR SECTION "B-B"

1. ACCESS HATCH SHALL BE SIZED TO ALLOW FOR INSTALLATION AND REMOVAL OF GRINDER UNIT.
2. ALL BOLTED CONNECTION (INCLUDING PIPE FLANGES) INSIDE THE WETWELL SHALL BE MADE USING STAINLESS STEEL BOLTS, NUTS, AND WASHERS.
3. ALL WETWELLS MUST BE CONCENTRIC.
4. ENGINEER SHALL ENSURE WETWELL HAS SUFFICIENT CONCRETE FOR ANCHORING. SEE PLAN VIEW & SECTION "B-B" FOR SUBMERSIBLE PUMPS AND PIPING.
5. STATION SHALL MEET REQUIREMENTS FROM NCDEQ INCLUDING ELEVATION AND/OR PROTECTION FROM FLOODING.

TOWN OF APEX
STANDARDS
EFFECTIVE: MARCH 23, 2021

SEWAGE GRINDER UNIT (WET WELL INSTALLATION)

STD. NO.
800.03
SHEET 1 OF 2