



NOTES:

1. CONCRETE SHALL BE 3000 PSI.
2. CONTRACTION JOINTS SHALL BE SPACED AT 10' INTERVALS OR 15' INTERVALS WHEN A MACHINE IS USED.
3. EXPANSION JOINTS SHALL BE SPACED AT 50' INTERVALS.
4. FINISH ALL CONCRETE WITH CURING COMPOUND.
5. FOLLOW ALL APPLICABLE ACI REQUIRMENTS.
6. VALLEY CURB SHALL ONLY BE USED FOR APPROVED APPLICATIONS.

**TOWN OF APEX
STANDARDS**

EFFECTIVE: FEBRUARY 28, 2023

CONCRETE CURB AND GUTTER

STD. NO.

300.03

SHEET 1 OF 1